

REQUEST FOR PROPOSALS

Sealed proposals for the **South Kennedy Street and Fortner Road sewer extension** will be received by the City of Metter at Metter City Hall, located at 49 South Rountree Street, Metter, Georgia until **3:00 PM on June 26, 2019**. All bids will be publicly opened and read aloud at that time.

The work to be done consists of 275 LF of 8" PVC sewer line, 1 manhole and Jack and Bore 40LF of 8" DIA steel casing pipe with 4" DIA MJDI carrier pipe with 4" PVC clean out on S. Kennedy St. and 290 LF of 8" PVC sewer line, 1 manhole and (3) 4" sewer laterals with clean outs on Fortner Road. All work shall be completed within **30 calendar days** from the Notice to Proceed, which is expected within 15 days of the bid opening. There will be a non-mandatory pre-bid meeting on June 5, 2019 at 10:00 AM at Metter Public Works.

A drawing can be picked up at Metter Public Works located at 25 South Terrell Street.

Bids must be accompanied by a Bid Bond and shall be secured by a surety company, certified check or cashier's check in an amount equal to at least 10% of the amount of the bid. A contract performance and payment bond each in the amount of 100% of the contract amount will be required of the successful bidder. Bidders must also submit at least 5 references of work that has been done in reference to this project.

The Owner reserves the right to reject any and all bids and to waive any informality in the bidding.

The contractor, or any subcontractor, submitting a bid for utility contracting, as defined in O.C.G.A. Section 43-14-2 to a utility system as defined in said section, shall conform to O.C.G.A. Section 43-14-8.2 et seq. with reference to Utility Contractor's Licenses and shall submit the bid with the license numbers, as issued by the Division of Utility Contractors, affixed on the outside of the bid envelope.

All bids are to be enclosed in a sealed envelope and addressed as follows:

**S. Kennedy St./Fortner Road Sewer Extension Project
CITY OF METTER
P. O. Box 74, 49 S. ROUNTREE STREET
METTER, GEORGIA 30439
ATTENTION: MISSY EDENFIELD, PURCHASING MANAGER**

Mark the outside of the envelope as follows:

PROJECT NAME: S. Kennedy St./Fortner Road Sewer Extension Project

S. KENNEDY ST./FORTNER ROAD SEWER EXTENSION

ITEM DESCRIPTION	EST. QTY	UNIT	UNIT PRICE	TOTAL
Mobilization	1	LS		
8" PVC SDR 35 sewer line	565	LF		
Jack and Bore 8" DIA steel casing pipe (min. wall thickness .250") with 4" DIA MJDI carrier pipe with 4" PVC stubout lateral.	40	LF		
Sanitary Manhole 4' to 6' Deep	2	EA		
Connect to existing sanitary manhole	2	EA		
4" Sewer laterals with Clean Outs	3	EA		
TOTAL CONSTRUCTION PRICE				